



Proposal and Contract

# Esary Roofing and Siding

www.esary.com

License #: ESARYRS175KE

420 Pease Rd \* Burlington, WA 98233 \* (360) 757-0933 FAX (360) 757-0932 \* info@esary.com

## PROPOSAL SUBMITTED TO:

Date: June 2, 2026

|          |                     |              |                                          |
|----------|---------------------|--------------|------------------------------------------|
| Name:    | Joe Wolford         | Job Number:  | 16763                                    |
| Company: |                     | Job Address: | 667 Bear Cove Road, Deer Harbor WA 98243 |
| Address: | 596 Bear Cove Road  | City:        | Deer Harbor, WA 98243                    |
| City:    | Eastsound, WA 98245 | Estimator:   | Mike Jorve                               |
| Home:    | (360) 982-9705      | Cell:        |                                          |

DESCRIPTION OF WORK: The contractor proposes to furnish materials, tools, equipment, and supplies and to perform labor in a substantial and workmanlike manner, which includes a description of materials to be used on the job, as follows: Re-roof main house.

- Removal and disposal of vegetation and growing medium will be performed by others.
- Remove 1 layer of existing roofing down to the roof deck, dispose of old roofing, dump fee included.
- Pound or pull all existing fasteners. Clear off the roof deck and inspect for structural soundness.
- If any dry rot is discovered, it will be replaced at \$85.00 per man hour + material (Time and Material Rate) It is impossible to determine the severity of rot until the roof is removed.
- **(OPTION)** Install 2" polyiso rigid insulation over existing substrate (R 11.4)
- Install 50 mil Duro-Last PVC single-ply roof membrane system.
  - **COLOR:** \_\_\_\_\_
- Seal around all roof penetrations.
- Install PVC-clad drip metal.
- At the end of the day, the job site will be left in a neat, professional manner.
- All roofing and related debris is hauled away and disposed of properly and legally, leaving your premises clean.

## SPECIAL NOTES:

\*All travel and lodging will be invoiced at cost when the project is completed. Costs are not included in this bid.

\*During the removal and installation of the roofing system, there may be areas where exposed ceilings exist and dust or debris may be able to filter into the building or attic space. Owner understands and agrees to prepare for this by covering items under exposed ceilings. Owner also recognize that debris may enter into the attic or in other areas inside the building is unavoidable and will not hold the Contractor responsible for that particular clean up.

\* Normal roofing operations may cause unavoidable noise and vibration. To prepare for roofing, the Contractor recommends that all wall or ceiling hangings be secured or removed during the roofing project.

| <b>Estimate</b>                            | <b>Amount</b>        | <b>Warranties</b>                      |
|--------------------------------------------|----------------------|----------------------------------------|
| 50 mil Duro-Last PVC single ply membrane   | \$53,850.00 plus tax | 20 year Duro-Last, 10 year workmanship |
| 1/2" CDX plywood, if required (Add)        | \$12,048.00 plus tax |                                        |
| 2" Polyisocyanurate rigid insulation (Add) | \$15,517.50 plus tax |                                        |

**This proposal is good for 14 days.** If not withdrawn by Esary Roofing & Siding Co. Inc., the quote given above is subject to change at the sole discretion of Esary Roofing & Siding Co. Inc. You, the buyer, may cancel this transaction at any time before midnight of the third business day after the date of this transaction. If canceled after the 3 business days, there will be a 15% cancellation fee based on the total of the estimate/contract. This covers material restocking fees, schedule changes, and administration costs.

Esary Roofing is not responsible for certain circumstances or product conditions. More specifically, it should be noted that oil canning of metal may occur. The cause is steel mill production tolerances, which are characteristic, not defects. This condition may be even more apparent in flat pan configurations and is not a cause for rejection of the material. Asbestos removal is the responsibility of the owner. Foreign objects on the roof, including, but not restricted to: TV dishes, solar panels, signs & etc., are the responsibility of the owner. Skylights: Esary Roofing is not responsible for the replacement of any old or homemade style skylights or damage resulting from the removal or installation of roofing near the same.

**STATE SALES TAX will be added when applicable. Additional dump fees may be required. Permit fees will be added per code requirements.**

**PAYMENT TERMS: 50% of the contract is due upon signing**

**REMAINING BALANCE: Due upon completion of the job.**

**OVERDUE AMOUNTS will be charged a 1.50% per month finance charge**

Authorization to proceed with work:

I, the undersigned, am the owner or authorized representative of the premises listed herein. I hereby authorize the described work at the price listed above. I agree to pay for the services at the time they are completed. I understand that a 3% credit card handling fee will be charged when paying with a credit card. I shall pay for all associated fees at the posted rates. By the addition of my signature below, I agree that I have received a copy of the contract, and notice to the owner, and that I have read, understand, and agree to the terms listed herein.

By: Mike Jowe

By: \_\_\_\_\_

Date: 6/2/2026

Date: \_\_\_\_\_

SKAGIT CO. 360-757-0933  
WHATCOM CO. 360-318-0604  
KING CO. 206-546-5336  
SAN JUAN CO. 360-468-3278  
STATE WIDE 1-800-735-7183



420 PEASE ROAD, BURLINGTON WA 98233

FAX 360-757-0932  
ESARY\*RS175KE  
www.esary.com  
info@esary.com

#### NOTICE TO CUSTOMER

This contractor is registered with the State of Washington, registration no. ESARYRS175KE has posted with the state a bond or deposit of \$12,000.00 for the purpose of satisfying claims against the contractor for breach of contract, including negligent or improper work in the conduct Of the contractor's business. The expiration date of this contractor's registration is 5/12/2026.

#### **THE BOND OR DEPOSIT MIGHT NOT BE SUFFICIENT TO COVER A CLAIM THAT MIGHT ARISE FROM THE WORK DONE UNDER YOUR CONTRACT.**

This bond or deposit is not for your exclusive use because it covers all work performed by this Contractor. The bond or deposit is intended to pay valid claims up to \$12,000.00 that you and Other customers, suppliers, subcontractors, or taxing authorities may have.

#### **FOR GREAT PROTECTION, YOU MAY WITHHOLD A PERCENTAGE OF YOUR CONTRACT.**

You may withhold a contractually defined percentage of your construction contract as retainage for a stated period to provide protection to you and help ensure that your project will be completed as required by your contract.

#### **YOUR PROPERTY MAY BE LIENED.**

Suppose a supplier of materials used in your construction project, or an employee or subcontractor of your contractor of subcontractors, is not paid. In that case, your property may be liened to force payment, and you could pay twice for the same work.

#### **FOR ADDITIONAL PROTECTION, YOU MAY REQUEST THE CONTRACTOR TO PROVIDE YOU WITH ORIGINAL "LIEN RELEASE" DOCUMENTS FROM EACH SUPPLIER OR SUBCONTRACTOR ON YOUR PROJECT.**

The contractor is required to provide you with further information about lien release documents if you request it. General information is also available from the State Department of Labor and Industries. I have received a copy of this disclosure statement.

By: \_\_\_\_\_

Date: \_\_\_\_\_